

. ZUX40 Dove Mat White
: Wall Tile Factory
Production Group
Recommend ed Use
General Properties
Report Date

. ZUX40 Dove Mat White
: Wall Tile Factory
: Dry-pressed ceramic tiles / Group BIII / GL
: Interior walls
: Mat
: 14 02 2007

Test Title	Test Results	Requirements	Desicion
Length & Width (mm)	199,5 – 200,2 mm	199,1 – 201,0 mm	OK
	399,3 – 400,0 mm	398,5 – 400,5 mm	
Thickness (mm)	7,0 mm	6,7 – 7,3 mm	OK
Straightness of Sides (%)	< %0,2	± %0,3	OK
Rectangularit y (%)	< %0,2	± %0,5	OK
Edge Curvature (%)	< %0,2	+ %0,5 / - %0,3	OK
Corner Curvature (%)	< %0,2	± %0,5	OK
Center Curvature (%)	< %0,2	+ %0,5 / - %0,3	OK
Surface Quality	First Quality	> %95 perfect	OK
Water Absorption	>13,00 % - < 15,00 %	10 % < E ≤ 20 %	OK
Breaking Strength (N)	> 400 N	> 200 N	OK
Modulus of Rupture (N/mm²)	>21 N/mm ²	> 15 N/mm ²	OK
Coeff. Of Thermal Expansion	< 7,0 x 10 ⁻⁶	As declared	OK
Thermal Shock Resistance	Resistant	Required	OK
Crazing Resistance	Resistant	Required	OK
Frost Resistance	NPD	Available	OK
Coefficient of Friction (µ)	NPD	Only for floor tiles	OK
Moisture Expansion (mm/m)	< 0,3	As declared	OK
Impact Resistance	NPD	As declared	OK
Staining Resistance	Class 5	Min. class 3	OK
Resistance to low conc. of Acid & Alkalis	В	As declared	OK
Resistance to high conc. of Acid & Alkalis	В	As declared	OK
Household Chemicals	A	Min. B	OK
Release of Cadmium	< 0,07 mg/dm ²	As declared	OK
Release of Lead	< 0;8 mg/dm ²	As declared	OK
OVERALL RESULT	All test results are positive according to the norms of		
	ISO 13006 and EN 14411 standards, Annex L.		
_			

Prepared by Kağan Kurnaz Quality Assurance Staff

Approved by Ahmet Pehlivan Quality Assurance Manager